Sl. No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Roofing with existing tiles and reepers allowing 15 per cent for wastage.	Sqr.	10 0 0	5·61	56
15	Plastering with chunam mortar ...	„	4 0 0	40·20	161
16	Chacolate painting	„	4 8 0	8·64	39
17	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	„	35 0 0	11·45	400
18	White washing	Lump	sum	..	50
19	Cutting grooves in joints of old and new masonry work.	Lump	sum	...	10
20	Repairs to the existing roof and 1st floor ...	Lump	sum	...	30
21	Providing dias and other necessities of the Court.	Lump	sum	...	200
	Total ...	...	..	...	3,009
	Contingencies ..	...	...	..	191
	Grand Total ...	...	...	...	3,200

L. A. H. WINCKLER,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for constructing Sub-Registrar's Office and Bonded Warehouse at Kunigal, published in the *Mysore Gazette* dated 5th January 1928, Part VI, pages 6 and 7. The last date of presenting the tender is 28th January 1928.

V. V. PATANKAR,
Executive Engineer.

HASSAN DIVISION.

Dated 17th December 1927.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 5th January 1928. The last date for receiving tender is 24th January 1928."

Dated 29—30th December 1927.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette* of the 5th instant, advertising the date of tender will be received."

R. L. STEELE,
Executive Engineer,

CHITALDRUG DIVISION

Abstract Notification.

The attention of the public is hereby invited to the advertisement page No. 12 and 13 of the *Mysore Gazette* of 5th January 1928, calling for tenders for the work of constructing a Town Hall Building at Harihar in Harihar Sub-Taluk.

A. TANDONI RAO,
Executive Engineer.

KADUR DIVISION.

FORM OF ADVERTISEMENT.

Notification dated 13th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 6th February 1928, for constructing an anicut across the Gowrihalla, near Halasabalu, Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

256

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 2 to 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing an anicut across the Gowrihalla, near Halasabalu, Chikmagalur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity for constructing masonry anicut across the Gowrihalla near Halasabalu, Chikmagalur Taluk.

Serial No.	Details of work	Unit	Quantity
1	Earthwork excavation mixed of slushy soil ...	C.yds.	1654
2	Do filling, watering and tamping, etc. ...	,,	146
3	Stone jelly concrete in surki mortar	C.ft.	4278
4	Burnt size stone in surki mortar	,,	6693
5	Burnt stone slabs new 6" thick dressed and set in surki-mortar.	S.ft.	636
6	Cutting groove (3" x 2") for seating of gate ...	R.ft.	5
7	Rough stone work with masonry jelly packing and wedging.	C.yds.	303
8	Cutting slit (6" x 3") for gate on top	R.ft.	2
9	Rough stone work old, with masonry new jelly packing and wedging apron.	C.yd.	264
10	Removing silt and clearing channel bed	Lump sum	
11	Clearing site and cutting trees, etc.	,,	
12	Cutting goggles and fixing slab in surki mortar ...	No.	54
13	Pointing with cement	S.qr	23·88
14	Bailing water	Lump sum	
15	Filling jelly beneath apron	C.yd.	98
16	Providing and fixing teakwood shutter 2" thick with iron straps and rod and locking arrangements, etc., complete.	S.ft.	3·10
	Extending right return in continuation of the head sluice.		
1	Earthwork excavating foundation	C.yd.	15
2	Stone jelly surki concrete	C.ft.	169
3	Burnt size stone in surki mortar	,,	242
4	Burnt stone slabs 6"	S.ft.	23

B. R. GARUDACHAR
Executive Engineer.